



Leveraging MLCP for Seamless Hotel Renovation

PROJECT AT A GLANCE:

- 78-Bed Hotel on Folkstone Sea Front
- Hotel remained open during renovation
- 1,500m + MLCP installed
- ~1000 press-fit fittings
- 16-75mm MLC pipework



"Multipipe's MLCP system was a game-changer for the Folkestone hotel project. The flexibility of the pipe allowed us to work around existing structures, minimising disruption to the hotel's operations. The ease of installation and the reliability of the system ensured a smooth and efficient project delivery."

Mike
Heritage Gas

OBJECTIVE



Heritage Gas was tasked with a complex plumbing and heating renovation project at a 78-bed hotel on the Folkestone seafront. The project presented a unique challenge: the hotel needed to remain operational throughout the entire renovation process. This meant the existing plumbing system had to be maintained while the new system was installed.

SOLUTION



Heritage Gas recognised the flexibility and efficiency of Multipipe's MLCP system as the ideal solution for this project. The phased approach, involving floor-by-floor installation, ensured minimal disruption to the hotel's operations.

Key features of the project included:

- **Core Pipework Installation:** A robust core pipework system was installed, serving as the backbone of the new plumbing infrastructure.
- **Manifold System:** A carefully designed manifold system was implemented in the loft spaces, allowing for easy isolation of individual rooms for maintenance or repairs.
- **MLCP Pipe Range:** The project utilised Multipipe's full range of MLCP pipes, from 16mm to 75mm, ensuring optimal performance and flexibility.

Because of specialist nature of the project, the collaboration between Heritage Gas and Multipipe was key to the project's success. By working together, we were able to ensure the larger pipe, as well as all the fittings required were going to be available and delivered on time.

MULTIPIPE